

CITY OF PORT ST. JOE, FLORIDA
NOTICE TO RECEIVE SEALED BIDS
RFP 2018-01

Sealed bids for City of Port St. Joe for “Equipment Trailer – Public Works” will be received at City Hall, 305 Cecil G. Costin Sr. Blvd., Port St. Joe, Florida 32456 up until 3:00 PM EST, Friday, February 16, 2018. Bids will be publicly opened and acknowledged, Friday, February 16, 2018, at 3:05 PM EST, in the City Commission Chambers.

Bids shall be submitted in a sealed envelope, plainly marked with bidder’s name, address, date and time of opening, and bid number for “RFP 2018-01 Equipment Trailer – Public Works”.

DESCRIPTION OF WORK: Direct Purchase of an equipment trailer as further described in the bid description document. The bid description document is available at www.cityofportstjoe.com.

For questions concerning this project, please contact John Grantland at 850-229-8247.

The City of Port St. Joe reserves the right to accept or reject any and all Statements of Bids in whole or in part, to waive informalities in the process, to obtain new Statements of Bids, or to postpone the opening pursuant to the City’s purchasing policies. Each Statement of Bid shall be valid to the City of Port St. Joe for a period of sixty (60) days after the opening.

The City of Port St. Joe is an Equal Opportunity Employer

NOTICE TO PUBLISHER: This legal ad is to appear on Thursday, February 1, 2018, and Thursday, February 8, 2018 in the Star Newspaper.

Please forward the original “Proof of Publication” and the invoice to:

The City of Port St. Joe

Attn: Charlotte Pierce

P.O. Box 278

Port St. Joe, FL 32457

RFP 2018-01
“Equipment Trailer – Public Works”
Bid Description

The City of Port St Joe is requesting Bids for the direct purchase of a 25K gooseneck equipment trailer with the standards or options as described below:

1. 20 foot flat deck with a 5 foot self-cleaning dove tail outside edge. Trailer shall be 102” wide.
2. LED Lights
3. Load Range G 14 ply radial tires
4. Storage with lid
5. Dual 12K 2 speed jacks
6. D rings
7. Sealed wiring harness
8. Closed back grommets
9. Oak deck with Penofin wood treatment
10. 2 – 10K Dexter axels with 12K springs
11. 6X36 hydraulic ramps
12. The following steel will be the minimum standard used for construction: 12” I beam 19# per foot, 4” I beam CM 16”C 80K yield, 8’ C side rails.
13. Paint color will be black.